


Tile Assembly Procedure


From Margherita opening to
Margherita closing





- Materials:
 - Tile base, sidewall metalized
 - Tile window, antimony, metalization
 - Stack of MCPs


Product:
A sealed tile


Let's make a seal!





















Then poof!



Thermal Cycle


Procedure and times

- Assemble tile In-Situ: 2 hours
- Bolt, close, leak check 1 hour
- Pump down to $\sim 0.5 \times 10^{-6}$ Torr ~ 12 hours (overnight)

- Slow heat through seal (~200C goal) 6 hours
- Increase to max temp (~300C goal) 3 hours
- Long bake (at 300C) 16 hours
- Cooldown 8 hours

Total = 48 hours

M11: Tubulated tile #9



Why *this* procedure

- Indium melts at 157C
 - Higher temperature is better wetting
- Getter activation takes some time (?)
 - So do the longest time, worst case scenario
- Constraint: 300C for 16 hours is the *frit* limit

That's it

- Thermal cycle is in an infant stage
 - More constraints to be discovered

Thank you